

GEOCAL, INC.

GEOSCIENCES & ENGINEERING

7290 South Fraser Street

Centennial, Colorado 80112-4286

Phone: 303-337-0338 Fax: 303-337-0247



30% DESIGN SOIL AND FOUNDATION INVESTIGATION

**Proposed
6th Avenue Freeway over BNSF Bridge
Replacement
City and County of Denver, Colorado**

Prepared For

**Wilson & Company, Inc.
Attn: Scott Waterman, P.E.
999 18th Street, Suite 2600
Denver, Colorado 80202**

**December 19, 2011
Revised March 9, 2012**

GEOCAL, INC.

GEOSCIENCES & ENGINEERING

7290 South Fraser Street

Centennial, Colorado 80112-4286

Phone: 303-337-0338 Fax: 303-337-0247



30% DESIGN SOIL AND FOUNDATION INVESTIGATION

Proposed 6th Avenue Freeway over BNSF Bridge Replacement City and County of Denver, Colorado

Prepared For

By: Walter J. Zitz, EI
Staff Engineer

And By: Gabriel A. Burgess, P.E.
Senior Engineer

Reviewed by: Ronald J. Vasquez, P.E.
Principal Engineer

**Wilson & Company, Inc.
Attn: Scott Watterman, P.E.
999 18th Street, Suite 2600
Denver, Colorado 80202**

**December 19, 2011
Revised March 9, 2012**

G10.1354.002

TABLE OF CONTENTS

	Page
1.0 PURPOSE AND SCOPE.....	1
2.0 PROPOSED CONSTRUCTION	2
3.0 SITE CONDITIONS	2
4.0 SITE GEOLOGY.....	3
5.0 SUBSURFACE INVESTIGATION	4
6.0 SUBSURFACE CONDITIONS	5
7.0 LABORATORY TESTING.....	6
8.0 PRELIMINARY FOUNDATION RECOMMENDATIONS.....	8
8.1 DRIVEN PILES.....	9
8.2 DRILLED SHAFTS.....	9
8.3 LATERAL LOAD CAPACITY	10
9.0 RETAINING STRUCTURES.....	11
9.1 GRAVITY AND CANTILEVER WALLS.....	12
9.2 SOIL NAIL WALLS.....	13
10.0 SEISMIC DESIGN PARAMETERS.....	13
11.0 UNDERDRAIN SYSTEM.....	14
12.0 SITE GRADING.....	15
13.0 PRELIMINARY PAVEMENT DESIGN	16
14.0 LIMITATIONS.....	19

LIST OF FIGURES, TABLES AND APPENDIXES

Figure 1	Locations of Exploratory Borings
Figure 2	Logs of Exploratory Borings
Figure 3	Legend and Notes for Exploratory Borings
Figures 4 through 7	Swell-Compression Test Results
Figures 8 through 10	Gradation Test Results
Figures 11 through 13	R-Value Test Reports
Figures 14 through 24	Unconfined Compression Tests
Table 1	Summary of Laboratory Test Results
Table 2	Summary of Laboratory Chemical Analysis Results
APPENDIX A	Laboratory Test Results Colorado Analytical Laboratories, Inc.
APPENDIX B	Preliminary Pavement Design Data and Analysis

1.0 PURPOSE AND SCOPE

This 30% design level report contains the results of a preliminary soil and foundation investigation conducted for the proposed replacement of the existing three-span 6th Avenue Bridge over Burlington Northern Santa Fe (BNSF) Railroad in Denver, Colorado. The project is being conducted under the Colorado Bridge Enterprise Program administered under the direction of the Colorado Department of Transportation (CDOT). Affected rights-of-way are controlled by City and County of Denver, BNSF Railroad, and CDOT.

A field subsurface investigation was conducted to obtain information on pavement, soil, bedrock, and ground water conditions. Soil and bedrock samples were visually classified, and selected samples were laboratory tested to evaluate strength, compressibility or swell characteristics, classification, and chemical properties. The results of the field and laboratory investigations were analyzed to develop preliminary recommendations for foundations, retaining walls, and pavements. We understand that this project will be continued under a design/build procedure and that the design/build contractor will be responsible for final design. The investigation was conducted in general accordance with our Subconsultant Agreement/Subcontract No. 001 (WCI File No. 11-100-30102) with Wilson & Co., Inc, dated March 11, 2011. The investigation is identified by CDOT as "Task Order #2 "Preliminary Design of 6th Ave Bridge over BNSF Railroad".

This report has been prepared to summarize the data obtained and to present our preliminary conclusions and recommendations based on the proposed construction and the subsurface conditions encountered. Design parameters and a discussion of geotechnical engineering considerations related to construction of the proposed structures are included. Limited environmental monitoring and sampling was conducted by Pinyon Environmental during Geocal's drilling operations. More specific investigations related to possible hazardous materials are beyond the scope of this study.

2.0 PROPOSED CONSTRUCTION

The proposed construction is expected to consist principally of replacing the existing bridge with a similar two-span structure with abutments and piers to be near their current locations. New retaining walls will likely be cast-in-place cantilevered or possibly soil nail. Changes to the approach embankment fills and new deck alignment are expected to be minor. New pavements may be constructed for the (bridge) approaches, but grades are expected to be similar to existing.

3.0 SITE CONDITIONS

The project site is situated on the transition between lower terraces of the eastern pre-controlled floodplain of the South Platte River and upper terraces associated with slightly elevated ground (sometimes referred to as Lincoln Park Uplands) between the South Platte River and Cherry Creek Valley. The original natural terraces have been modified during the development of transportation, industrial-commercial, and drainage control projects in the area. The north-flowing South Platte River is about one-half mile west of the site and separated from the site by the 6th Avenue/I-25 Interchange. 6th Avenue within the project area is elevated on constructed embankments and bridge structures, continuously from west of the South Platte to North Klamath Street on the east.

The bridge crosses over a rail corridor having two mainline and two siding heavy rail tracks. Tracks are all under the wider west span with rail beds about 25 feet below bottom of girders. The east span is underlain by steep concrete slope pavement extending from near track level to just below the bridge girders. Embankment side slopes near the bridge are covered with sparse grass, weeds, brush and scattered deciduous trees. Areas east of the bridge are occupied by light industrial and warehouse-type businesses in low-rise structures; land to the west is essentially dedicated to I-25 right-of-way.

4.0 SITE GEOLOGY

Standard quadrangle-scale published geologic mapping indicates that natural (pre-construction) unconsolidated surficial and shallow deposits include:

1. Near river floodplain soil assigned to the Post-Piney Creek Alluvium generally as interbeds and mixtures of humic clay, silt, sand, and occasional small gravel. Thicknesses of 5 feet to 10 feet are typical (where not removed by construction). Local, but significantly thick lenses of highly humic bog clays and silt have been noted. Mapping indicates Post-Piney Creek soil covered the surface west of the current track corridor.
2. The upper floodplain terrace soil identified as Piney Creek Alluvium and typified as well stratified clay, silt and sand (including mixtures of) that are commonly humic in the uppermost and gravelly near the base. The Piney Creek Alluvium has been reported as 5 feet to 10 feet thick, mapped as originally covering the surface east of the tracks, and indicated as extending under portions of Post-Piney Creek deposits.
3. Older upper terrace deposits assigned to Broadway Alluvium as moderately well-graded sand and gravel with generally limited fines. These deposits are mapped on higher terraces east and west of the South Platte River and interpreted as commonly extending under Piney Creek and Post-Piney Creek soils in the project area.

The above soil deposits are indicated to lie on well-stratified sedimentary bedrock assigned to the Denver-Arapahoe Formations (undifferentiated). At depths associated with potential construction, members of the formations are typically dominated by claystone and siltstone interbeds with lesser interbeds and lenses of sandstone. Outcrops or construction excavated exposures of this material are mapped within a mile of the project site, and are referred to in published reports of nearby soil borings and water wells. Published mapping indicates bedrock to have about 20 feet of natural alluvium cover (excluding embankment fills) in the vicinity of the bridge and to be flat to very gently dipping.

5.0 SUBSURFACE INVESTIGATION

The subsurface investigation for this project included drilling eight exploratory borings from October 31, 2011 through February 24, 2012 at the approximate locations shown on Figure 1, Locations of Exploratory Borings. Initial borings (Borings 1 through 6), were advanced with a truck-mounted CME-75 drill rig equipped with 3¼ inch inside diameter (ID) hollow stem augers. Two borings (7 and 8) were drilled at approximate track level, within the BNSF right-of-way and were advanced with a truck-mounted CME-550 equipped with 3¼ inch inside diameter hollow stem augers. All borings were logged by a representative of Geocal. Subsurface soil and bedrock samples were obtained using 2 inch ID California liner samplers and 1¾ inch ID split-spoon (Standard Penetration Tester) samplers. The samplers were driven into the various strata with blows from a 140 pound hammer, similar to ASTM D1586 test standard. Penetration resistance values when properly evaluated indicate the relative consistency or density of the soils, or hardness of bedrock. Drive samples were taken at approximately 5 foot to 10 foot intervals. Larger bulk samples of auger cuttings were collected from about the upper 1 foot to 10 feet of selected borings.

Logs of the conditions encountered are shown on Figure 2, Logs of Exploratory Borings. Description of the materials and symbols used on the logs are presented on Figure 3, Legend and Notes for Exploratory Borings.

During drilling of portions of Borings 1 and 6, a representative of Pinyon Environmental, Inc. (Pinyon) conducted limited environmental hazmat monitoring and sampling. While drilling approximately 15 feet above and below groundwater level in these borings, open hole air, auger cuttings, and drive samples were monitored for total organic compounds and explosive limits using a field-portable photo ionization detector. Additionally, bailed samples of groundwater were collected once groundwater was encountered in the borings. The results of the field and laboratory investigations performed by Pinyon are reported elsewhere.

6.0 SUBSURFACE CONDITIONS

As shown on the Figure 2, the subsurface conditions varied slightly. In general, the borings encountered relatively thick sections of man-placed embankment fill (artificial fill) followed by natural mostly granular soils over sedimentary (claystone) bedrock. Five of the six borings drilled from the 6th Avenue street level were drilled through roadway or shoulder pavement consisting of 7 inches to 10 inches of asphalt; no specifically identified aggregate base course material was encountered. Boring 1 was drilled in off-road right-of-way (near the northwest corner of the bridge), and Borings 7 and 8 were drilled in sparse grass-covered BNSF right-of-way, near track level.

Borings 1 through 6 encountered man-placed embankment fill to depths of about 35 feet to 39 feet deep. The fill generally consisted of loose to medium dense slightly clayey to silty sand to gravelly sand that included medium stiff to stiff sandy clay. The fill was generally medium to coarse grained, with small to large gravel, and had low to high plasticity for the clay portions, was moist, and light to dark brown. Asphalt, construction debris, and pieces of glass were found in the lower portions of the fill in some of the borings. Borings 7 and 8, encountered artificial fill at the surface to depths of about 3 feet to 8 feet deep. The fill consisted of clay with silt, sand, and trace gravel, that was medium stiff, had low plasticity, and was moist.

Below the fill, the borings encountered natural medium dense (with some loose and very dense zones) gravel with sand, silt and some clayey zones. In Borings 1, 7, and 8, medium dense sands with some gravel were encountered and silt with sand and some organics was encountered in Boring 6. The gravel was small to medium sized and was rounded to sub-rounded.

In Borings 1 through 6, sedimentary bedrock was encountered from depths of about 48 feet to 53 feet, and extended to the maximum depth explored, 85 feet. Bedrock was encountered at 20 feet and 23½ feet in Borings 7 and 8. The bedrock was comprised of claystone that was very hard, had medium to high plasticity, contained varying amounts of silt and fine grained sand, was moist, and blue to dark grey. The claystone contained some small interbedded lenses of sandstone.

Ground water was measured between about 32 feet and 40 feet in Borings 1 through 6 immediately after drilling. Ground water was measured at about 10 feet and 11 feet deep immediately after drilling Borings 7 and 8. The ground water level had changed little after 1 day in Boring 1. Groundwater levels may fluctuate significantly depending on seasonal precipitation and levels of the South Platte River flow. Borings were backfilled with gravel and cement mixture after drilling (with the exception of Borings 1, 7 and 8) and compacted with the weight of the drill rig. Borings 1, 7, and 8 were backfilled with auger cuttings and compacted after drilling. The borings conducted in 6th Avenue were patched with at least 9 inches of Transpatch© High Strength Early set grout that was mixed on site.

7.0 LABORATORY TESTING

Laboratory tests conducted on selected soil and bedrock samples consisted of natural moisture contents, dry densities, liquid and plastic limits (Atterberg Limits), grain size distribution (gradation), swell-compression, unconfined compression, R-value, water-soluble sulfate concentrations, and chemical analysis. Laboratory test results are shown on Figures 4 through 24 and summarized on Tables 1 and 2.

Swell-Compression Tests: Swell-compression tests are a direct measurement of compressive or expansive potential for a particular sample when wetted. Measurements were made by loading the sample in a consolidometer to a light surcharge pressure, subjecting the sample to wetting, then allowing the specimen to swell or compress. After stabilization, additional loads were applied with each load increment given the opportunity to stabilize. Swell-compression tests were performed in accordance with local practice on samples of the fill consisting of clay and clayey sand and on claystone bedrock.

The results shown on Figures 4 through 7 indicate little or no swell potential under light load and wetting for the samples of soil and bedrock. A low to moderate compressibility under increased loading was also indicated.

Atterberg Limits and Gradations: Atterberg limits and gradation analyses were used to classify the soils according to the American Association of State Highway and Transportation Officials (AASHTO) classification system. These classifications provide a qualitative assessment of engineering properties. Gradation analysis and Atterberg Limits test results are presented on Figures 8 through 10.

The Atterberg Limits tests indicate that the man-placed (artificial) fill samples generally had low to high plasticity and underlying natural granular soil samples were mostly non-plastic. An elastic silt with sand was classified for a sample from Boring 6 at 34 feet. Tests on the underlying claystone bedrock samples showed medium plasticity.

The combined gradation and Atterberg Limits indicate that most of the fill samples classified as A-6 with some A-1-a material. The lower natural granular soil samples typically classified as A-1-b in accordance with the AASHTO system.

R-Value: Selected bulk samples from the upper embankment fill were tested for R-value, which is an indication of the ability of the soil to transfer traffic loading laterally. Figures 11 through 13 show R-values of 60, 62 and below 5 which indicate relatively high strength (and quality) to very low strength. The low value was from Boring 5 at 1 foot to 5 feet. Based on the test results, highly variable pavement support characteristics for the near surface embankment fill exists.

Unconfined Compressive Strength: The unconfined strength is a measurement of compressive strength under axial loading without lateral confinement. The test is useful in evaluating soil or bedrock foundation bearing capacities, and the results are shown on Figures 14 through 24. The values ranged from 3,910 pounds per square foot (psf) to 17,860 psf for the samples of claystone and sandstone bedrock, and 1,750 psf to 3,000 psf for sandy lean clay samples obtained from the embankment fill.

Water-Soluble Sulfates: The water-soluble sulfate test is a measurement of the potential degree of sulfate attack on concrete exposed to the onsite soils and bedrock. Sulfate solutions react with tri-calcium aluminate hydrate, which is a normal constituent of Portland Cement concrete, forming calcium sulfo-aluminate hydrate with an accompanying substantial volume expansion which causes cracking. Sulfate expansion problems will typically exist when the soils have concentrations in excess of 0.10%.

The concentrations of water-soluble sulfates measured on selected samples of soil and bedrock ranged from 0.02 to 0.18%. The test results indicate a Class 1 "Severity of Sulfate Exposure" in accordance with Table 601-2 of the Colorado Department of Transportation (CDOT) Standard Specifications for Road and Bridge Construction (2011 Edition). For preliminary design, Class 1 requirements as defined in Section 601.04 Sulfate Resistance should be used for concrete exposed to the near surface soils and bedrock encountered within the project area. During final design, additional sulfate concentration tests should be performed, as needed. Water soluble sulfate test results are summarized in Table 2.

Other Chemical Tests: Laboratory test results on selected samples of soil and bedrock indicate electrical resistivity in the range of approximately 170 ohm-cm to 5,000 ohm-cm, pH from 5.5 to 7.6, and chloride concentrations from 0.0015 percent to 0.2181 percent. Sulfides varied from positive to negative detection. Water soluble chloride concentrations and positive or negative sulfide presence were performed by Colorado Analytical Laboratories, Inc., and their results are contained in Appendix A. Remaining chemical tests were performed by Geocal, Inc. Test results are summarized in Table 2.

8.0 PRELIMINARY FOUNDATION RECOMMENDATIONS

Two foundation types, driven H-piles and drilled shafts, both supported by the underlying bedrock appear to be suitable for use at this site and for support of the new bridge structure. Driven H-piles will likely encounter refusal within a few feet of the bedrock surface and may be designed for the structural capacity of the piles. Drilled shafts will likely have to be installed using slurry and temporary casing to control ground water, caving, and potentially flowing material. The two foundation types are discussed in the following sections.

8.1 Driven Piles

Preliminary recommendations presented in this section are based on the "AASHTO LRFD Bridge Design Specifications" manual, the subsurface data obtained, our experience, and local geotechnical engineering practice. Installation of driven piles should be in accordance with Section 502 "Piling" of the *Standard Specifications for Road and Bridge Construction* (2011 or latest edition), by the Colorado Department of Transportation (CDOT standard specifications).

1. Piles may consist of heavy steel H-sections consisting of Grade A50 steel and driven to refusal in the underlying bedrock. Refusal criteria should be determined during construction using the Pile Driving Analyzer (PDA) in accordance with Section 502 of the CDOT specifications, latest edition.
2. The pile driving contractor should provide the results of a GRLWeap drivability analysis for the pile driving equipment proposed for use, and the type of pile in accordance with the CDOT specifications prior to pile driving operations.
3. Due to the presence of granular soils underlying the embankment, use of a driving shoe may be required to drive the pile through the granular soils and into the underlying bedrock.
4. A combined side shear and end bearing ultimate capacity of 45 kips per square inch (ksi) times the cross sectional area may be used for grade A50 steel for preliminary design. Load and resistance factors used for final design should be consistent with LFRD procedures, as established by AASHTO.

8.2 Drilled Shafts

Drilled shafts also appear feasible from a preliminary geotechnical consideration. Casing and slurry installation methods will be required to control caving and ground water. The design and construction criteria presented below should be observed for a drilled shaft foundation system. Installation should be in accordance with Section 503 – Drilled Caissons of the CDOT standard specifications.

- 1) For preliminary design, drilled shafts may be designed for a nominal tip bearing pressure of 140,000 psf and ultimate side shear value of 14,000 psf for that portion of the foundation in competent bedrock. Load factors used for final design should be consistent with current LFRD procedures as established by AASHTO. A tip resistance factor of 0.55, and a side resistance factor of 0.60 should be applied to the above nominal soil bearing capacity recommendations, as determined by O'Neill and Reese (1999) for drilled shafts in Intermediate Geomaterials (IGMs).

- 2) The presence of water and caving soils encountered in the exploratory borings indicates that casing and slurry construction methods will be required to reduce water infiltration and caving. If water cannot be removed, or if it is impractical to remove the water prior to placement of concrete, then concrete should be placed using an approved tremie method. The contractor should be advised that water bearing sandstone layers may be encountered.

8.3 Lateral Load Capacity

The following preliminary recommendations are based on the structural engineer using the computer program LPILE for the lateral load analysis. We recommend that the bedrock be modeled as hard clay. Lateral capacity parameters are presented below to allow the structural engineer to evaluate possible soil-structure responses under varying conditions and assumptions.

**Preliminary Lateral Capacity Parameters
For Drilled Shaft or Driven Pile Foundations**

Soil Type	Total Unit Weight (pcf)	Cohesion, c (psf)	Friction Angle (ϕ)	k-static (pci)	ϵ_{50}
Artificial Fill (Embankment Soils)	125	0	20	70-100	0.020
Natural Granular Soils (Submerged)	65	0	30	125	---
Bedrock	125	5,000	0	2,000-3000	0.003


Reductions in lateral capacity for loading perpendicular to the line of shafts or piles will not be required if center to center spacing of 5 shaft or pile diameters or more between adjacent drilled shafts or piles is maintained.

For lateral loads parallel to the line of shafts/piles, reduction in lateral capacity is necessary at a spacing less than 6 diameters. LPILE uses p-multipliers to account for reduced capacity of closely spaced drilled shafts or piles for loading in either direction. Data presented below are from Article 10.7.2.4 of the 2007 AASHTO LRFD Bridge Design Specifications 4th Edition Manual. A sketch of the loading and how the rows are referenced is also shown.

P-Multipliers
Drilled Shaft or Driven Pile Foundation

Center to Center Spacing	p-multiplier for LPILE		
	Row 1	Row 2	Row 3 and Higher
3B	0.7	0.5	0.35
4B	0.85	0.67	0.52
5B	1	0.85	0.70

B= Diameter of Shaft or Pile



9.0 RETAINING STRUCTURES

The recommendations presented below should be considered preliminary. Additional explorations, analysis, and design recommendations may be required once retaining wall types, locations, and geometries have been established. We have assumed that at least new wing walls may be needed at the bridge abutments.

9.1 Gravity and Cantilever Walls

Gravity or cantilevered retaining walls should be supported by the same foundation type as the bridge foundations (driven piles or drilled shafts). Retaining structures that are laterally supported and can be expected to undergo only a slight amount of deflection should be designed for lateral earth pressures based on the "at-rest" earth pressure condition. Cantilevered or gravity retaining structures which rotate and/or deflect sufficiently to mobilize the internal soil strength of the wall backfill may be designed for the "active" earth pressure condition. The following ultimate earth pressure coefficients may be used for imported Class 1 material to be used as backfill.

Material	Active (K_a)	At-Rest (K_o)	Passive (K_p)	γ_T – Unit Weight (pcf)	Friction Angle (ϕ), degrees
Imported Class 1	0.28	0.44	3.54	130	34

Lateral wall movements or rotation of at least 0.1% of the wall height is typically required to develop the full active case, whereas lateral movement of at least 2% of the wall height is normally required to establish the full passive case assuming granular Class 1 backfill. Suitable factors of safety should therefore be applied to the above ultimate values to limit strain needed to reach ultimate strength, particularly with passive resistance where large strains are needed to mobilize full resistance. Imported material should meet CDOT Class 1 structure backfill grading requirements. Equivalent fluid unit weights should be taken as follows:

$$\begin{array}{llll}
 \text{Above ground water:} & \gamma_{eq} & = & \gamma_T \times K_{a,o,p} \\
 \text{Below ground water:} & \gamma_{eq} & = & (\gamma_T - 62.4) \times K_{a,o,p} \\
 \text{where} & \gamma_T & = & \text{soil total unit weight} \\
 & K_{a,o,p} & = & \text{appropriate earth pressure coefficient}
 \end{array}$$

The above parameters are for a horizontal backfill and no surcharge loading. Foundation and retaining structures should be designed for appropriate surcharge pressures such as from traffic, etc. The buildup of water behind a wall or an upward sloping backfill surface will increase the lateral pressure imposed on retaining structures. An under-drain should be provided to help prevent hydrostatic pressure buildup, unless the wall is designed to accommodate the additional pressure.

Care should be taken not to over-compact the backfill or use large equipment adjacent to the wall because this could cause excessive lateral wall loading.

9.2 Soil Nail Walls

Soil nail walls installed in the embankment fill appear to be feasible from a geotechnical consideration. Most of the soil encountered in the embankment areas were granular with variable amounts of clay and silt. Final design of soil nail walls should be developed using parameters determined with site specific subsurface investigations and appropriate laboratory analyses. Procedures developed by the Federal Highway Administration should be used for design, construction and testing.

For feasibility or preliminary evaluations of soil nail walls, the length of the nails may be assumed to be about 70% of the wall height. The following additional parameters may be assumed for preliminary design.

Total Unit weight (pcf), γ_T	125
Friction angle (degrees), ϕ	28
Cohesion (psf), C	200

10.0 SEISMIC DESIGN PARAMETERS

The structure is located at Latitude 37.725746 and Longitude 105.010884 within the South Platte River Terrace Deposits. The borings conducted by Geocal indicate that the underlying soils generally consisted of relatively deep (35 feet to 39 feet) man-placed artificial fill (silty to clayey sand with gravel) underlain by natural soils (sand and gravel with some clay and silt) to depths of 48 feet to 53 feet. Very hard claystone bedrock was encountered below the natural soils and extended to the maximum depth explored, 85 feet. We have assumed that the bridge will be supported by either drilled shafts or driven piles

extended into the underlying claystone bedrock. Based on the amount of overburden soils present, the Seismic Site Class utilized for analysis should be Site Class D (stiff soils). There is low potential for liquefaction of the soils encountered below the groundwater table in a seismic event; however, any potential liquefaction should have limited effect on the bridge structure's foundations because the foundations will be supported by bedrock and the depth of potentially liquefiable material is nominal.

The nearest potentially active fault identified based on United States Geological Survey (USGS) is the Ute Pass Fault zone which is located approximately 32 miles to the southwest. Other seismic hazards such as ground rupture or faulting and slope instability have low risk of occurrence at the site. The bridge should be deemed a critical structure based on the expected usage.

Utilizing the AASHTO Specifications for LRFD Seismic Bridge Design, the site is classified as "D" and the seismic zone as "1" using Tables 3.10.3.1-1 and 3.10.6-1, as shown in the LRFD design guidelines. Using the AASHTO Earthquake Motion Parameters program, the seismic design spectrum plots were created for Spectral Acceleration vs. Time and Spectral Acceleration vs. Spectral Displacement for the site Class B and Site Class D responses. We have attached the printouts of the graphs and data generated from the AASHTO program in Appendix B. For preliminary design, the following parameters may be utilized for design of the bridge structure:

- ◆ Peak Ground Acceleration (PGA): 0.059 – Site Class B
- ◆ Spectral Acceleration Coefficient at 0.2 Seconds (S_s): 0.126 – Site Class B
- ◆ Spectral Acceleration Coefficient at 1.0 Seconds (S_1): 0.034 – Site Class B
- ◆ Modified Peak Ground Acceleration (A_s): 0.095 – Site Class D
- ◆ Modified Spectral Acceleration Coefficient at 0.2 Seconds (SD_s): 0.202 – Site Class D
- ◆ Modified Spectral Acceleration Coefficient at 1.0 Seconds (SD_1): 0.081 – Site Class D

11.0 UNDERDRAIN SYSTEM

Below grade structures should be provided with an underdrain system which will help prevent buildup of hydrostatic pressures. The underdrain system should consist of a perforated PVC pipe

surrounded by free draining granular material placed at the bottom of the wall backfill and sloped at a minimum 1% grade to a suitable gravity outlet. Free draining granular material used in the drain system should conform to the requirements for Class B filter material as specified in the CDOT standard specifications.

12.0 SITE GRADING

Based on the materials encountered, excavation of the onsite materials should be possible with conventional heavy duty excavating equipment. Most of the embankment material is expected to be granular (sand and gravel) with mixed clays and silts. The natural soils below the embankment fill are expected to be mostly sands and gravels. Site grading activity should be conducted in accordance with the Colorado Department of Transportation *Standard Specifications for Road and Bridge Construction* (latest edition).

The re-use of onsite materials will be a function of what the intended use is. Most of the material is expected to be granular, although some clays and organic material should be anticipated. Clays and organic material should be kept outside of areas planned for pavements, structure backfill, or use as fill for support of structures. Soils used for support of pavements should meet the minimum strength requirements as specified during final design.

Permanent un-retained cuts in the overburden soils up to 10 feet high should be no steeper than 3:1 horizontal to vertical grade unless evaluated individually. The risk of slope instability will be significantly increased if seepage is encountered in cuts. If seepage on slopes is encountered, stability should be evaluated. Good surface drainage should be provided around permanent cuts to direct surface runoff away from the cut face. Cut slopes and other stripped areas should be protected against erosion by vegetation or other methods.

Fill slopes should be constructed no steeper than 3:1 horizontal to vertical grade provided the fills are properly compacted and drained. The ground surface underlying proposed fills should be carefully prepared by removing organic matter, scarifying to a depth of 12 inches and re-compacting in accordance

with the CDOT standard specification. Fills should be benched into hillsides that are steeper than 4 horizontal to 1 vertical. Settlement of embankments constructed of granular material similar to that encountered onsite and properly compacted, should be less than 1% of the embankment height and essentially occur during construction.

If sloped excavations are used, stockpiled material should be placed no closer than 10 feet to the top of the excavation. Sloped and braced excavations should conform to applicable OSHA regulations, and the contractor should assume responsibility for an excavation that is safe for workers.

13.0 PRELIMINARY PAVEMENT DESIGN

A pavement section is a layered system designed to distribute concentrated traffic loads to the subgrade without overstressing the subgrade soils. Performance of the pavement structure is a function of a number of factors including but not limited to the physical properties of the subgrade soils, drainage, climate, and traffic loading. The preliminary pavement sections presented in this section are based on laboratory test results and CDOT and AASHTO design procedures, and apply to the 6th Avenue approaches to the bridge.

Traffic Loading and ESAL Calculations: The CDOT web site was used to obtain Annual Average Daily Traffic Volumes for 6th Avenue from near the intersection of Sheridan Boulevard. These volumes were then utilized to determine the 20 year 18 kip Equivalent Single Axle Loadings (ESAL₂₀) for asphalt pavement, and the 30 year ESAL₃₀ for concrete pavements. The CDOT website presents the route and reference points (mile posts) and provides the traffic data for those points and when data was gathered. The data is displayed as annual average daily traffic (AADT) with breakdown of single unit trucks and combination unit trucks. Information from the website is included in Appendix B.

For preliminary design, we assumed a 3% annual traffic growth rate. Traffic volumes were projected 20 years and 30 years based on the 2010 traffic data. Based on the CDOT website, vehicle

distributions were 96.5% passenger vehicles, 2.4% single unit trucks, and 1.1% combination unit trucks. A design lane factor of 30% was used to distribute the total traffic across the 6 lanes, (3 lanes in each direction).

An 18 kip Equivalent Single Axle Load (ESAL) is the equivalent 18,000 pound axle loading for the different vehicle types. The design ESAL is the total number of equivalent loadings to either asphalt or concrete pavements over the design period. The design ESALs presented here should be considered preliminary and will need to be checked during final design with more specific and current traffic data. The following values were calculated (included in Appendix B): $ESAL_{20} = 8,284,671$ for asphalt (HMAP) and $ESAL_{30} = 13,769,951$ for concrete (PCCP).

General Design Parameters: The following summarizes the pavement design parameters used:

General

Initial Serviceability	4.5
Terminal Serviceability	2.5
Reliability	95%
Drainage Coefficient	1.0
Growth rate	3.0%

Concrete

Overall Standard Deviation	0.34
Loss of Support	1.0
Modulus of Rupture	650 psi
Concrete Modulus of Elasticity	3.4 million psi
Load Transfer Coefficient (doweled and tied)	2.8
$ESAL_{30}$	13,769,951

Asphalt

Structural Coefficient (HMAP)	0.44
Structural Coefficient (ABC)	0.12
$ESAL_{20}$	8,284,671

Subgrade Soil Strength Coefficients: The pavement subgrade soils encountered classified between A-1-a and A-6 in accordance with the AASHTO classification system. Laboratory R-values measured from 62 to less than 5, indicating a high variability for the pavement subgrade soil in the approach areas. Good to very poor subgrade support characteristics could be exposed during construction. For design purposes, we assigned an R-value of 50, indicating that any poor subgrade (R-

value less than 50) encountered within the pavement areas will need to be subexcavated a minimum of 3 feet and replaced with R-50 or better material.

A resilient modulus of 13,168 was determined based on the CDOT equations 2.1 and 2.2 in the 2012 CDOT Pavement Design Manual. For rigid pavement thickness calculations, a k-value (modulus of vertical subgrade reaction) of 175 pounds per cubic inch (pci) was chosen based on Table 2.3 of the design manual. The strength values used for pavement design are summarized as follows:

<u>R-Value</u>	<u>Resilient Modulus (psi)</u>	<u>k-value (pci)</u>
50	13,168	175

Pavement Thickness Recommendations: Hot Mix Asphalt Pavement (HMAP) thickness sections were calculated using AASHTOWare DARWin software, following CDOT and AASHTO guidelines. Portland Cement Concrete Pavement (PCCP) thickness sections were calculated using the AASHTO 1998 Rigid Pavement Design Guide software provided by the FHWA.

The recommended pavement thickness sections shown below are for R-value 50 material in the upper 3 feet of the subgrade, 20 year design for asphalt pavement (HMAP), 20 year design for asphalt over aggregate base course (ABC) pavement, and 30 year design for concrete pavement (PCCP). Design printouts are included in Appendix B.

<u>Full depth HMAP (inches)</u>	<u>HMAP over ABC (inches)</u>	<u>PCCP over ABC (inches)</u>
9 ½	7 ½ over 6	11 ¼ over 6

A 6 inch layer of aggregate base course should be used to support concrete pavements. This ABC layer will help control the effect of fines migration through the joints and subsequent loss of support.

During final design the HMAP, PCCP and ABC pavement sections should be checked with more current data. The design should meet the requirements of the Colorado Department of Transportation (CDOT) and/or the standards of the Metropolitan Government Pavement Engineers Council (MGPEC) as applicable.

14.0 LIMITATIONS

This 30% design level report has been prepared in accordance with generally accepted geotechnical engineering practices in this area, and is provided for use by the client for preliminary design purposes. The conclusions and recommendations submitted in this report are based upon the data obtained from the exploratory borings drilled at the approximate locations shown on Figure 1. Additional explorations for the structures, walls, and pavements are recommended for final design. The nature and extent of variations between the borings may not become evident until excavation is performed.

Geocal's professional services were performed using the degree of care and skill ordinarily exercised by reputable geotechnical engineers practicing in this or similar environments. No warranty expressed or implied is made. Geocal is not responsible for the interpretation of the site surface and subsurface conditions by others that are not consistent with the contents of this report.

Investigations into the occurrence or potential occurrence of hazardous materials, or other environmental assessments that may be applicable to the site are beyond the scope of services represented by this report. On-site observation of excavations and foundation bearing strata and testing of geotechnical materials by a representative of this office is recommended.












FIGURE 1

BORING 1 BORING 2 BORING 3 BORING 4 BORING 5 BORING 6 BORING 7 BORING 8



LEGEND


- 8 1/2  ASPHALT, approximate thickness in inches indicated in the top left corner.
-  FILL, gravel and sand with silt, trace clay, occasionally cobbles, medium dense with some loose zones, moist, fine to coarse grained sand, small to large gravel, light to dark brown, some asphalt, glass, and construction debris.
-  SAND with GRAVEL, medium dense, medium to coarse grained sand, small gravel, wet, brown.
-  SAND and SILT, dense, fine grained, low plasticity, wet, black to dark brown, some organic material.
-  GRAVEL, medium dense to very dense, small to medium gravel, rounded to sub-rounded, wet, brown to dark brown, some clay and sand seams.
-  CLAYSTONE BEDROCK, mostly with slight sand and slight silt to silty, very hard, slightly moist, blue to dark gray, very fine to fine grained sand.



NOTES


- Borings 1 through 6 were drilled on October 31 to November 9, 2011 with CM-75 drill rig equipped with 3 1/4 inch inside diameter hollow-stem augers. Borings 7 and 8 were drilled February 24, 2012 with a CME-550 drill rig equipped with 3 1/4 inch inside diameter hollow-stem augers.
- Location of borings shown on Figure 1 are approximate.
- The lines between strata represent approximate boundaries between material types. Transitions between materials may actually be gradual.
- Boring logs are drawn to elevation.
- Water level readings shown on the logs were made at the time and under conditions indicated, fluctuations in the water level may occur with time.

SWELL-COMPRESSION TEST



Sample Location	Boring 1
Sample Depth	24 feet
Sample Description	Sandy lean clay, fill
USCS Classification	CL
AASHTO Classification	

Dry Density	107 pcf
Moisture Content	20.7 %
Volume Change	0.1 %
Swell Pressure	0 psf



Sample Location	Boring 1
Sample Depth	59 feet
Sample Description	Claystone bedrock
USCS Classification	
AASHTO Classification	

Dry Density	112 pcf
Moisture Content	17.3 %
Volume Change	0.8 %
Swell Pressure	1,030 psf

GEOCAL, INC.

6th Avenue over BNSF


JOB NO. G10.1354.002

SWELL - COMPRESSION TEST RESULTS

FIGURE NO.


4

SWELL-COMPRESSION TEST



Sample Location	Boring 3
Sample Depth	34 feet
Sample Description	Fat clay with sand, fill
USCS Classification	CH
AASHTO Classification	A-7-6(25)

Dry Density	92 pcf
Moisture Content	32.9 %
Volume Change	0.1 %
Swell Pressure	0 psf



Sample Location	Boring 4
Sample Depth	24 feet
Sample Description	Clayey sand with gravel, fill
USCS Classification	SC
AASHTO Classification	

Dry Density	110 pcf
Moisture Content	17.4 %
Volume Change	0.0 %
Swell Pressure	0 psf

GEOCAL, INC.


6th Avenue over BNSF

JOB NO. G10.1354.002

SWELL - COMPRESSION TEST RESULTS


FIGURE NO. 5

SWELL-COMPRESSION TEST



Sample Location	Boring 4
Sample Depth	54 feet
Sample Description	Sandstone bedrock
USCS Classification	
AASHTO Classification	

Dry Density	112 pcf
Moisture Content	16.3 %
Volume Change	0.1 %
Swell Pressure	0 psf



Sample Location	Boring 5
Sample Depth	54 feet
Sample Description	Claystone bedrock
USCS Classification	
AASHTO Classification	

Dry Density	110 pcf
Moisture Content	16.0 %
Volume Change	0.0 %
Swell Pressure	0 psf

GEOCAL, INC.


6th Avenue over BNSF

JOB NO. G10.1354.002

SWELL - COMPRESSION TEST RESULTS

FIGURE NO. 6

SWELL-COMPRESSION TEST



Sample Location	Boring 6
Sample Depth	49 feet
Sample Description	Claystone bedrock
USCS Classification	
AASHTO Classification	

Dry Density	110 pcf
Moisture Content	15.6 %
Volume Change	0.5 %
Swell Pressure	0 psf

GEOCAL, INC.

6th Avenue over BNSF

JOB NO. G10.1354.002

SWELL - COMPRESSION TEST RESULTS

FIGURE NO. 7

PERCENT FINER




	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	21	15	16.5413	6.7271	3.5052	0.5704	0.1380			
□	NV	NP	2.5776	1.4893	1.2374	0.7341	0.3329	0.2202	1.64	6.76
△	37	16	0.5136	0.1281						
◇	37	15	4.6349	0.2307	0.1268					
▽	44	18	0.2588							

Project No. G10.1354.002 Client: Wilson & Company Project: 6th Avenue over BNSF		Remarks:
○ Location: Boring 1	Depth: 1-10 feet Sample Number: 5815-1	
□ Location: Boring 1	Depth: 49 feet Sample Number: 5815-4	
△ Location: Boring 2	Depth: 4 feet Sample Number: 5830-1	
◇ Location: Boring 2	Depth: 34 feet Sample Number: 5830-2	
▽ Location: Boring 3	Depth: 4 feet Sample Number: 5820-1	

Remarks:	
----------	--

Gradation Test Results



GRAIN SIZE - mm.

	% +3"	% Gravel	% Sand		% Silt		% Clay
○	0	3	23		74		
□	0	24	62		14		
△	0	16	75		9		
◇	0	4	44		52		
▽	0	17	78		5		


	LL	PL	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	57	23	0.2980							
□	NV	NP	9.0089	1.9535	1.1056	0.3205	0.0898			
△	NV	NP	5.3989	1.2371	0.8253	0.3876	0.1670	0.0879	1.38	14.08
◇	40	16	0.6410	0.1200						
▽	NV	NP	5.2220	2.1705	1.5958	0.6967	0.2735	0.1762	1.27	12.32

Material Description								USCS	AASHTO
○ fat clay with sand, fill								CH	A-7-6(25)
□ silty sand with gravel								SM	A-1-b
△ well-graded sand with silt and gravel								SW-SM	A-1-b
◇ sandy lean clay, fill								CL	A-6(9)
▽ well-graded sand with silt and gravel								SW-SM	A-1-b

Project No. G10.1354.002 Client: Wilson & Company			Remarks:
Project: 6th Avenue over BNSF			
○ Location: Boring 3	Depth: 34 feet	Sample Number: 5820-3	
□ Location: Boring 3	Depth: 44 feet	Sample Number: 5820-4	
△ Location: Boring 4	Depth: 39 feet	Sample Number: 5820-8	
◇ Location: Boring 5	Depth: 1-5 feet	Sample Number: 5830-4	
▽ Location: Boring 5	Depth: 44 feet	Sample Number: 5830-5	

GEOCAL, INC.

Gradation Test Results



	% +3"		% Gravel		% Sand		% Silt		% Clay	
○	0		26		53		21			
□	0		0		39		61			
△	0		0		28		72			
◇	0		0		9		91			
▽	0		23		55		22			
×	LL	PL	D85	D60	D50	D30	D15	D10	C _c	C _u
○	26	16	9.0144	1.6148	0.7630	0.1975				
□	41	16	0.2258							
△	52	31	0.1159							
◇	43	23								
▽	23	12	6.6759	1.9694	1.0602	0.1167				

Material Description	USCS	AASHTO
○ clayey sand with gravel, fill	SC	A-2-4(0)
□ sandy lean clay, fill	CL	A-7-6(12)
△ elastic silt with sand	MH	A-7-5(16)
◇ claystone bedrock	CL	A-7-6(20)
▽ clayey sand with gravel	SC	A-2-6(0)

Project No. G10.1354.002 **Client:** Wilson & Company


Project: 6th Avenue over BNSF

○ Location: Boring 6	Depth: 1-5 feet	Sample Number: 5830-7
□ Location: Boring 6	Depth: 14 feet	Sample Number: 5830-8
△ Location: Boring 6	Depth: 34 feet	Sample Number: 5830-9
◇ Location: Boring 6	Depth: 49 feet	Sample Number: 5830-10
▽ Location: Boring 8	Depth: 4 feet	Sample Number: 5971-3

Remarks:

GEOCAL, INC.

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - AASHTO T 190

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psf	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	300	131.6	5.2	9	102	2.41	148	34	32
2	350	129.0	7.3	17	38	2.45	385	73	73
3	350	129.2	6.3	26	26	2.50	644	80	80

Test Results	Material Description
R-value at 300 psi exudation pressure = 61	poorly graded gravel with silty clay and sand, fill
Project No.: G10.1354.002 Project: 6th Avenue over BNSF Location: Boring 1 Sample Number: 5815-1 Depth: 1-10 feet Date: 2/28/2012	Tested by: H. Redzic Checked by: G. Burgess, P.E. Remarks: Test performed in accordance with Colorado procedures CP-L 3101 & 3102
R-VALUE TEST REPORT Geocal, Inc.	Figure 11

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - AASHTO T 190

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psf	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.

Test Results	Material Description
R-value at 300 psi exudation pressure = n/a	sandy lean clay, fill
Project No.: G10.1354.002 Project: 6th Avenue over BNSF Location: Boring 5 Sample Number: 5830-4 Depth: 1-5 feet Date: 2/28/2012	Tested by: H. Redzic Checked by: G. Burgess, P.E. Remarks: Sample extruded from under the mold during the exudation portion of test prior 800 psi. R Value < 5.
R-VALUE TEST REPORT Geocal, Inc.	Figure 12

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - AASHTO T 190

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psf	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	150	123.9	8.5	9	120	2.42	112	21	20
2	350	125.2	7.9	22	51	2.47	312	64	64
3	350	124.3	7.1	44	39	2.50	553	72	72

Test Results	Material Description
R-value at 300 psi exudation pressure = 62	clayey sand with gravel, fill
Project No.: G10.1354.002 Project: 6th Avenue over BNSF Location: Boring 6 Sample Number: 5830-7 Depth: 1-5 feet Date: 2/28/2012	Tested by: H. Redzic Checked by: G. Burgess, P.E. Remarks: Test performed in accordance with colorado procedures CP-L 3101 & 3102.
R-VALUE TEST REPORT Geocal, Inc.	Figure 13

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	6980			
Undrained shear strength, psf	3490			
Failure strain, %	2.5			
Strain rate, in./min.	0.05			
Water content, %	16.2			
Wet density, pcf	134.0			
Dry density, pcf	115.3			
Saturation, %	98.6			
Void ratio	0.4346			
Specimen diameter, in.	1.94			
Specimen height, in.	3.95			
Height/diameter ratio	2.04			

Description: claystone bedrock

LL = 42 **PL = 23** **PI = 19** **Assumed GS= 2.65** **Type:**

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 1


Sample Number: 5815-5 **Depth:** 54 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

Figure 14

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	17857			
Undrained shear strength, psf	8928			
Failure strain, %	5.0			
Strain rate, in./min.	0.05			
Water content, %	16.3			
Wet density, pcf	133.6			
Dry density, pcf	114.8			
Saturation, %	98.2			
Void ratio	0.4411			
Specimen diameter, in.	1.94			
Specimen height, in.	3.97			
Height/diameter ratio	2.05			

Description: claystone bedrock

LL = 46

PL = 24

PI = 22

Assumed GS= 2.65

Type:

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 1


Sample Number: 5815-7

Depth: 64 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	6531			
Undrained shear strength, psf	3265			
Failure strain, %	9.4			
Strain rate, in./min.	0.05			
Water content, %	15.9			
Wet density, pcf	121.1			
Dry density, pcf	104.5			
Saturation, %	72.2			
Void ratio	0.5828			
Specimen diameter, in.	1.94			
Specimen height, in.	3.61			
Height/diameter ratio	1.86			

Description: claystone bedrock

LL = 43

PL = 26

PI = 17

Assumed GS= 2.65

Type:

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 2

Sample Number: 5830-3


Depth: 54 feet

UNCONFINED COMPRESSION TEST

Figure 16

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1752			
Undrained shear strength, psf	876			
Failure strain, %	14.4			
Strain rate, in./min.	0.05			
Water content, %	22.6			
Wet density, pcf	122.0			
Dry density, pcf	99.5			
Saturation, %	90.5			
Void ratio	0.6629			
Specimen diameter, in.	1.94			
Specimen height, in.	3.76			
Height/diameter ratio	1.94			

Description: sandy lean clay, fill

LL = 44	PL = 18	PI = 26	Assumed GS = 2.65	Type:
----------------	----------------	----------------	--------------------------	--------------

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 3


Sample Number: 5820-1 **Depth:** 4 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

Figure 17

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	11996			
Undrained shear strength, psf	5998			
Failure strain, %	3.4			
Strain rate, in./min.	0.05			
Water content, %	17.3			
Wet density, pcf	129.8			
Dry density, pcf	110.7			
Saturation, %	92.6			
Void ratio	0.4947			
Specimen diameter, in.	1.94			
Specimen height, in.	4.08			
Height/diameter ratio	2.10			

Description: claystone bedrock

LL = 47	PL = 26	PI = 21	Assumed GS= 2.65	Type:
---------	---------	---------	------------------	-------

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 3


Sample Number: 5820-5 **Depth:** 59 feet

UNCONFINED COMPRESSION TEST

Figure 18

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	3002			
Undrained shear strength, psf	1501			
Failure strain, %	8.0			
Strain rate, in./min.	0.05			
Water content, %	21.0			
Wet density, pcf	124.2			
Dry density, pcf	102.7			
Saturation, %	90.8			
Void ratio	0.6113			
Specimen diameter, in.	1.94			
Specimen height, in.	3.98			
Height/diameter ratio	2.05			

Description: sandy lean clay, fill

LL = 47

PL = 18

PI = 29

Assumed GS= 2.65

Type:

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 4

Sample Number: 5820-6


Depth: 9 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

Figure 19

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	8745			
Undrained shear strength, psf	4372			
Failure strain, %	4.0			
Strain rate, in./min.	0.05			
Water content, %	18.5			
Wet density, pcf	129.5			
Dry density, pcf	109.3			
Saturation, %	95.5			
Void ratio	0.5132			
Specimen diameter, in.	1.94			
Specimen height, in.	3.99			
Height/diameter ratio	2.06			

Description: claystone bedrock

LL = 40 **PL = 20** **PI = 20** **Assumed GS= 2.65** **Type:**

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 4


Sample Number: 5820-9 **Depth:** 49 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

Figure 20

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	3911			
Undrained shear strength, psf	1955			
Failure strain, %	4.4			
Strain rate, in./min.	0.05			
Water content, %	17.5			
Wet density, pcf	128.7			
Dry density, pcf	109.5			
Saturation, %	90.8			
Void ratio	0.5110			
Specimen diameter, in.	1.94			
Specimen height, in.	4.06			
Height/diameter ratio	2.09			

Description: claystone bedrock

LL = 48

PL = 24

PI = 24

Assumed GS= 2.65

Type:

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 6

Sample Number: 5830-11


Depth: 54 feet

UNCONFINED COMPRESSION TEST

Figure 21

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	13952			
Undrained shear strength, psf	6976			
Failure strain, %	4.9			
Strain rate, in./min.	0.05			
Water content, %	18.2			
Wet density, pcf	126.9			
Dry density, pcf	107.3			
Saturation, %	89.3			
Void ratio	0.5413			
Specimen diameter, in.	1.94			
Specimen height, in.	4.12			
Height/diameter ratio	2.12			

Description: claystone bedrock

LL = 45 **PL = 28** **PI = 17** **Assumed GS= 2.65** **Type:**

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF


Location: Boring 7

Sample Number: 5971-2 **Depth:** 29

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	12996			
Undrained shear strength, psf	6498			
Failure strain, %	3.0			
Strain rate, in./min.	0.05			
Water content, %	18.4			
Wet density, pcf	130.2			
Dry density, pcf	109.9			
Saturation, %	96.7			
Void ratio	0.5054			
Specimen diameter, in.	1.94			
Specimen height, in.	4.01			
Height/diameter ratio	2.07			

Description: claystone bedrock

LL = 50

PL = 25

PI = 25

Assumed GS= 2.65

Type:

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 8

Sample Number: 5971-4


Depth: 24 feet

UNCONFINED COMPRESSION TEST

Figure 23

GEOCAL, INC.

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	10476			
Undrained shear strength, psf	5238			
Failure strain, %	8.5			
Strain rate, in./min.	0.05			
Water content, %	16.2			
Wet density, pcf	125.6			
Dry density, pcf	108.1			
Saturation, %	81.0			
Void ratio	0.5303			
Specimen diameter, in.	1.94			
Specimen height, in.	4.24			
Height/diameter ratio	2.19			

Description: claystone bedrock

LL = 41	PL = 25	PI = 16	Assumed GS= 2.65	Type:
---------	---------	---------	------------------	-------

Project No.: G10.1354.002

Date Sampled:

Remarks:

Client: Wilson & Company

Project: 6th Avenue over BNSF

Location: Boring 8

Sample Number: 5971-5 **Depth:** 34 feet

UNCONFINED COMPRESSION TEST

GEOCAL, INC.

TABLE 1
SUMMARY OF LABORATORY TEST RESULTS

Client: **Wilson & Company**
Project Name **6th Avenue over BNSF**

Project # **G10.1354.002**

Sample Location		Natural Moisture Content (%)	Natural Dry Density (pcf)	Gradation		Percent Passing No. 200 Sieve	Atterberg Limits			Swell Pressure (psf)	Swell w/1or2 ksf Surcharge (%)	Unconfined Compressive Strength (psf)	R-Value at 300 psi Exudation Pressure	AASHTO Class (Group Index)	Soil or Bedrock Description
Boring No.	Depth (feet)			Gravel (%)	Sand (%)		Liquid Limit (%)	Plasticity Index (%)							
1	1-10			46	42	12	21	6					60	A-1-a	Poorly graded gravel with silty clay and sand, fill
1	24	20.7	107						0		0.1				Sandy lean clay, fill
1	34	20.2	101												Clayey sand with gravel, fill
1	49			4	92	4	NV	NP						A-1-b	Well-graded sand
1	54	16.2	116									6,980			Claystone bedrock
1	59	17.3	112						1,030		0.8				Claystone bedrock
1	64	16.3	115									17,860			Claystone bedrock
2	4	20.4	106	1	49	50	37	21						A-6(7)	Sandy lean clay, fill
2	34	15.0	119	15	44	41	37	22						A-6(4)	Clayey sand with gravel, fill
2	54	15.9	105									6,530			Claystone bedrock
3	4	22.6	100	2	35	63	44	26				1,750		A-7-6(14)	Sandy lean clay, fill
3	9	15.9	109												Silty, sandy clay with gravel, fill
3	34	32.9	92	3	23	74	57	34	0		0.1			A-7-6(25)	Fat clay with sand, fill
3	44			24	62	14	NV	NP						A-1-b	Silty sand with gravel
3	59	17.3	111									12,000			Claystone bedrock
4	9	21.0	103									3,000			Sandy lean clay, fill
4	24	17.4	110						0		0.0				Clayey sand with gravel, fill
4	39			16	75	9	NV	NP						A-1-b	Well-graded sand with silt and gravel
4	49	18.5	110									8,750			Claystone bedrock
4	54	16.3	112						0		0.1				Sandstone bedrock
5	1-5			4	44	52	40	24					<5	A-6(9)	Sandy lean clay, fill
5	44			17	78	5	NV	NP						A-1-b	Well-graded sand with silt and gravel
5	54	16.0	110						0		0.0				Claystone bedrock
6	1-5			26	53	21	26	10					62	A-2-4(0)	Clayey sand with gravel, fill
6	14	22.2	104	0	39	61	41	25						A-7-6(12)	Sandy lean clay, fill
6	34	50.5	68	0	28	72	52	21						A-7-5(16)	Elastic silt with sand
6	49	15.6	110	0	9	91	43	20	0		0.5				Claystone bedrock
6	54	17.5	110			91	48	24				3,910			Claystone bedrock
7	2	19.5	94			46	43	23						A-7-6(6)	Clayey sand with gravel
7	29	18.2	107			80	45	17				13,950			Claystone bedrock
8	4			23	55	22	23	11						A-2-6-(0)	Clayey sand with gravel
8	24	18.4	110			95	50	25				13,000			Claystone bedrock
8	34	16.2	108			81	41	16				10,480			Claystone bedrock

Sample Location		Natural Moisture Content (%)	Natural Dry Density (pcf)	Water Soluble Sulfates (%)	Laboratory Resistivity (ohm-cm)	pH	Chloride Water Soluble (%)	Sulfide	AASHTO Class. (Group Index)	Soil or Bedrock Description
Boring No.	Depth (feet)									
1	1-10			0.07	1,300	6.9	0.0256		A-1-a	Poorly graded gravel with silty clay and sand, fill
1	34	20.2	101	0.06	1,200	6.8	0.0180			Clayey sand with gravel, fill
1	49			0.07	4,500	7.0	0.0019		A-1-b	Well-graded sand
2	4	20.4	106	0.07	420	6.3	0.0696	Positive	A-6(7)	Sandy lean clay, fill
2	34	15.0	119	0.07	1,600	6.8	0.0021	Positive	A-6(4)	Clayey sand with gravel, fill
3	9	15.9	109	0.07	790	7.6	0.0196	Trace		Silty, sandy clay with gravel, fill
3	44			0.05	3,700	7.4	0.0030	Negative	A-1-b	Silty sand with gravel
4	9	21.0	103	0.18	490	6.9	0.0139	Positive		Sandy lean clay
5	54	16.0	110	0.06	680	6.7	0.0015	Positive		Claystone bedrock
6	14	22.2	104	0.13	460	6.7	0.0349	Trace	A-7-6(12)	Sandy lean clay
6	34	50.5	68	0.08	1,400	6.8	0.0079	Positive	A-7-5(16)	Elastic silt with sand
7	2	19.5	94	0.02	170	5.7	0.2181	Negative	A-7-6(6)	Clayey sand with gravel
8	4			0.03	5,000	5.5	0.0022	Negative	A-2-6(0)	Clayey sand with gravel

Appendix A

Laboratory Test Results

Colorado Analytical Laboratories, Inc.



Analytical Results

TASK NO: 111102009

Report To: Husein Redzic

Bill To: Husein Redzic

Company: Geocal

Company: Geocal

7290 S. Fraser St

7290 S. Fraser St

Centennial CO 80112

Centennial CO 80112

Task No.: 111102009
Client PO: 2976
Client Project: 6th Avenue over BNSF G10.1354.002

Date Received: 11/2/11
Date Reported: 11/9/11
Matrix: Soil - Geotech

Customer Sample ID B-1 @ 49 5815-4

Sample Date/Time:

Lab Number: 111102009-01

Test	Result	Method
Chloride - Water Soluble	0.0019 %	AASHTO T291-91/ ASTM D4327

Customer Sample ID B-1 @ 34 5815-3

Sample Date/Time:

Lab Number: 111102009-02

Test	Result	Method
Chloride - Water Soluble	0.0180 %	AASHTO T291-91/ ASTM D4327

Customer Sample ID B-1 @ 1-10 5815-1

Sample Date/Time:

Lab Number: 111102009-03

Test	Result	Method
Chloride - Water Soluble	0.0256 %	AASHTO T291-91/ ASTM D4327

Abbreviations/ References:

AASHTO - American Association of State Highway and Transportation Officials.

ASTM - American Society for Testing and Materials.

ASA - American Society of Agronomy.

DIPRA - Ductile Iron Pipe Research Association Handbook of Ductile Iron Pipe.

DATA APPROVED FOR RELEASE BY



Analytical Results

TASK NO: 111129004

Report To: Husein Redzic
Company: Geocal
7290 S. Fraser St
Centennial CO 80112

Bill To: Husein Redzic
Company: Geocal
7290 S. Fraser St
Centennial CO 80112

Task No.: 111129004
Client PO: 2993-1354
Client Project: 6th Ave. over BNSF G10.1354.002

Date Received: 11/29/11
Date Reported: 12/7/11
Matrix: Soil - Geotech

Customer Sample ID 5820-4 B-3 @ 44

Sample Date/Time:

Lab Number: 111129004-01

Test	Result	Method
Chloride - Water Soluble	0.0030 %	AASHTO T291-91/ ASTM D4327
Sulfide	Negative	AWWA C105

Customer Sample ID 5830-2 B-2 @ 34

Sample Date/Time:

Lab Number: 111129004-02

Test	Result	Method
Chloride - Water Soluble	0.0021 %	AASHTO T291-91/ ASTM D4327
Sulfide	Positive	AWWA C105

Customer Sample ID 5830-1 B-2 @ 4

Sample Date/Time:

Lab Number: 111129004-03

Test	Result	Method
Chloride - Water Soluble	0.0696 %	AASHTO T291-91/ ASTM D4327
Sulfide	Positive	AWWA C105

Customer Sample ID 5830-8 B-6 @ 14

Sample Date/Time:

Lab Number: 111129004-04

Test	Result	Method
Chloride - Water Soluble	0.0349 %	AASHTO T291-91/ ASTM D4327
Sulfide	Trace	AWWA C105

Abbreviations/ References:

AASHTO - American Association of State Highway and Transportation Officials.

ASTM - American Society for Testing and Materials.

ASA - American Society of Agronomy.

DIPRA - Ductile Iron Pipe Research Association Handbook of Ductile Iron Pipe.

DATA APPROVED FOR RELEASE BY



Analytical Results

TASK NO: 111129004

Report To: Husein Redzic

Bill To: Husein Redzic

Company: Geocal

Company: Geocal

Task No.: 111129004
Client PO: 2993-1354
Client Project: 6th Ave. over BNSF G10.1354.002

Date Received: 11/29/11
Date Reported: 12/7/11
Matrix: Soil - Geotech

Customer Sample ID 5830-9 B-6 @ 34

Sample Date/Time:

Lab Number: 111129004-05

Test	Result	Method
Chloride - Water Soluble	0.0079 %	AASHTO T291-91/ ASTM D4327
Sulfide	Positive	AWWA C105

Customer Sample ID 5830-6 B-5 @ 54

Sample Date/Time:

Lab Number: 111129004-06

Test	Result	Method
Chloride - Water Soluble	0.0015 %	AASHTO T291-91/ ASTM D4327
Sulfide	Positive	AWWA C105

Customer Sample ID 5820-2 B-3 @ 9

Sample Date/Time:

Lab Number: 111129004-07

Test	Result	Method
Chloride - Water Soluble	0.0196 %	AASHTO T291-91/ ASTM D4327
Sulfide	Trace	AWWA C105

Customer Sample ID 5820-6 B-4 @ 9

Sample Date/Time:

Lab Number: 111129004-08

Test	Result	Method
Chloride - Water Soluble	0.0139 %	AASHTO T291-91/ ASTM D4327
Sulfide	Positive	AWWA C105

Abbreviations/ References:

AASHTO - American Association of State Highway and Transportation Officials.
ASTM - American Society for Testing and Materials.
ASA - American Society of Agronomy.
DIPRA - Ductile Iron Pipe Research Association Handbook of Ductile Iron Pipe.

DATA APPROVED FOR RELEASE BY



Analytical Results

TASK NO: 120229001

Report To: Husein Redzic
Company: Geocal
7290 S. Fraser St
Centennial CO 80112

Bill To: Husein Redzic
Company: Geocal
7290 S. Fraser St
Centennial CO 80112

Task No.: 120229001
Client PO: 3062-1354
Client Project: 6th Ave. over BNSF G10.1354.000

Date Received: 2/29/12
Date Reported: 3/2/12
Matrix: Soil - Geotech

Customer Sample ID Geo 8 @ 4 Ft.

Sample Date/Time:

Lab Number: 120229001-01

Test	Result	Method
Chloride - Water Soluble	0.0022 %	AASHTO T291-91/ ASTM D4327
Sulfide	Negative	AWWA C105

Customer Sample ID Geo 7 @ 2 Ft.

Sample Date/Time:

Lab Number: 120229001-02

Test	Result	Method
Chloride - Water Soluble	0.2181 %	AASHTO T291-91/ ASTM D4327
Sulfide	Negative	AWWA C105

Abbreviations/ References:

AASHTO - American Association of State Highway and Transportation Officials.
ASTM - American Society for Testing and Materials.
ASA - American Society of Agronomy.
DIPRA - Ductile Iron Pipe Research Association Handbook of Ductile Iron Pipe.

DATA APPROVED FOR RELEASE BY

Appendix B

Preliminary Pavement Design Data and Analysis

Annual Average Daily Traffic (AADT) Volumes for Highway 006G

Route	Ref Pt	End Ref Pt	Length (Miles)	Annual Average Daily Traffic	AADT Year	AADT Single Trucks	AADT Comb Trucks	Percent Trucks	Design Hour Volume (% of AADT)	Daily Vehicle Miles Traveled	Segment Description
006G	282.333	283.469	1.106	115,000	2010	2750	1250	3.50	10	127,190	SHERIDAN BLVD INTERCHANGE STR (F-16-FL) - JCT SH 095A N AND S - RD N AND S (SHERIDAN BLVD) - - OVERPASS SEPARATION - LEAVE JEFFERSON COUNTY - LEAVE LAKEWOOD CITY LIMITS
006G	284.187	284.748	0.560	141,000	2010	2400	1700	2.90	8	78,960	MAJOR STR (F-16-EN) - RD N AND S (BRYANT ST) OVERPASS SEPARATION

Design Lane ESAL Calculations

6th Ave. Over BNSF			Vehicle Type/Classification (%)					
			Passenger Vehicles	Single Unit	Combination Unit			
Vehicle Type Load Factor (Flexible)			0.003	0.249	1.087			
Vehicle Type Load Factor (Rigid)			0.003	0.285	1.692			
			Number of Lanes = 6			% in Design Lane 30%		
Percent of types	Year	100.0%	96.5%	2.4%	1.1%			
"Current" ADT (CDOT provided)	2010	115,000	110,975	2,760	1,265			
"Future" ADT (Projected)	2035	240,784	Calculated Average Annual Increase			3.00%	25	Years between 'Current' & 'Future' ADT
Construction Year ADT	2014	129,433	124,903	3,106	1,424			
End Year ADT (Flexible)	2034	233,771	225,589	5,611	2,571			
End Year ADT (Rigid)	2044	314,169	303,173	7,540	3,456			
20-Yr Design ADT	2024	181,603	175,246	4,359	1,998			
Roadway ESAL (Flexible)	2029	27,615,571	3,837,887	7,923,354	15,854,330			
30-Yr Design ADT		221,801	214,038	5,323	2,440			
Roadway ESAL (Rigid)		45,899,838	4,687,432	11,074,502	30,137,904			
Design Lane ESAL (Flex)		8,284,671						
Design Lane ESAL (Rigid)		13,769,951						

1993 AASHTO Pavement Design

DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare Computer Software Product

Walter Zitz

Flexible Structural Design Module

6th Avenue over BNSF Bridge Replacement

Approach Pavements

Design Life: 20 Years (Asphalt)

Assume R-50 Subgrade

Flexible Structural Design

18-kip ESALs Over Initial Performance Period	8,284,671
Initial Serviceability	4.5
Terminal Serviceability	2.5
Reliability Level	95 %
Overall Standard Deviation	0.44
Roadbed Soil Resilient Modulus	13,168 psi
Stage Construction	1

Calculated Design Structural Number 4.02 in

Specified Layer Design

<u>Layer</u>	<u>Material Description</u>	Struct Coef. <u>(Ai)</u>	Drain Coef. <u>(Mi)</u>	Thickness <u>(Di)(in)</u>	Width <u>(ft)</u>	Calculated <u>SN (in)</u>
1	HMA	0.44	1	7.5	-	3.30
2	Class 6 ABC	0.12	1	6	-	0.72
Total	-	-	-	13.50	-	4.02

Layered Thickness Design

Thickness precision

Actual

<u>Layer</u>	<u>Material Description</u>	Struct Coef. <u>(Ai)</u>	Drain Coef. <u>(Mi)</u>	Spec Thickness <u>(Di)(in)</u>	Min Thickness <u>(Di)(in)</u>	Elastic Modulus <u>(psi)</u>	Width <u>(ft)</u>	Calculated Thickness <u>(in)</u>	Calculated <u>SN (in)</u>
1	HMA	0.44	1	-	-	-	-	9.14	4.02
Total	-	-	-	-	-	-	-	9.14	4.02

Rigid Pavement Design - Based on AASHTO Supplemental Guide

Reference: *LTPP DATA ANALYSIS - Phase I: Validation of Guidelines for k-Value Selection and Concrete Pavement Performance Prediction*

I. General

Agency: CDOT
Street Address: 6th Avenue over BNSF
City: Denver
State: Colorado

Project Number:

ID: 6th Avenue over BNSF

Description: Design of approach pavements to Bridge Structure

Location: Region 6

II. Design

Serviceability

Initial Serviceability, P1: 4.5
Terminal Serviceability, P2: 2.5

PCC Properties

28-day Mean Modulus of Rupture, (S'_c): 650 psi
Elastic Modulus of Slab, E_c : 3,400,000 psi
Poisson's Ratio for Concrete, m : 0.15

Base Properties

Elastic Modulus of Base, E_b : 15,000 psi
Design Thickness of Base, H_b : 6.0 in
Slab-Base Friction Factor, f : 1.4

Reliability and Standard Deviation

Reliability Level (R): 95.0 %
Overall Standard Deviation, S_0 : 0.34

Climatic Properties

Mean Annual Wind Speed, WIND: 8.8 mph
Mean Annual Air Temperature, TEMP: 50.3 °F
Mean Annual Precipitation, PRECIP: 15.3 in

Subgrade k-Value

175 psi/in

Design ESALs

13.8 million

Pavement Type, Joint Spacing (L)

☒ JPCP

☐ JRCP

☐ CRCP

Joint Spacing:

15.0 ft

JPCP

Effective Joint Spacing: 180 in

Edge Support

☒ Conventional 12-ft wide traffic lane

☐ Conventional 12-ft wide traffic lane + tied PCC

☐ 2-ft widened slab w/conventional 12-ft traffic lane

Edge Support Factor: 1.00

Sensitivity Analysis

Slab Thickness used for
Sensitivity Analysis: 10.84 in

☐ Modulus of Rupture

☐ Elastic Modulus (Slab)

☐ Elastic Modulus (Base)

☒ Base Thickness

☐ k-Value

☐ Joint Spacing

☐ Reliability

☐ Standard Deviation

Calculated Slab Thickness for Above Inputs:

10.84 in

Faulting

DOWELED PAVEMENT

Dowel Diameter: in
 K_d : psi/in
 E_s : psi

Base/Slab Frictional Restraint

- ☐ Stabilized Base
☒ Aggregate Base or LCB w/ bond breaker

ALPHA: /°F
 TRANGE: °F
 e : strain
 D : in
 P : lbf
 T :

Base Type

- ☐ Stabilized Base
☒ Unstabilized Base

FI: °F-days
 CESAL: million
 Age: years
 C_d :

Faulting (doweled)

0.06 in

Faulting Check - **PASS**

NONDOWELED PAVEMENT

Days90: days

D : in

Base Type

- ☐ Stabilized Base
☒ Unstabilized Base

FI: °F-days
 CESAL: million
 Age: years
 C_d :

Faulting (nondoweled)

in

Faulting Check -

Recommended critical mean joint faulting levels for design (Table 28)

Joint Spacing	Critical Mean Joint Faulting
< 25 ft	0.06 in
> 25 ft	0.13 in

Note: Joint load position stress checks need to be performed only for nondoweled pavements

Only two numbers need to be entered in this sheet:

Temperature gradient

Tensile stress at top of slab

Step 1:

Total Negative Temperature Differential

Slab Thickness: 10.84 in

Total Negative Temperature Differential: -6.3 °F

Construction Curling and Moisture Gradient Temperature Differential

Enter temperature gradient: °F/in (enter positive value from below)

For temperature gradient use:

Wet Climate: 0 to 2 °F/in (Annual Precipitation \geq 30 in or
Thornthwaite Moisture Index $>$ 0)

Dry Climate: 1 to 3 °F/in (Annual Precipitation $<$ 30 in or
Thornthwaite Moisture Index $<$ 0)

Total Effective Negative Temp. Differential: °F

Step 2:

Use one or more of the following charts to estimate the tensile stress at top of slab.

Note that the charts show the variation of tensile stress with negative temperature differential for slab thicknesses ranging from 7 to 13 in. These are plotted for a base course thickness of 6 in. The six charts represent three k-values (100, 250 and 500 psi/in) and two values for the elastic modulus of the base (25,000 psi and 1,000,000 psi). Use judgment to extrapolate the value of the tensile stress at the top of the slab from these charts.

Enter Tensile Stress at Top of Slab: psi (use charts below)

Step 3:

Compare the above tensile stress with the maximum tensile stress at the bottom of the slab for which the slab is designed. For the given inputs and the above thickness, this value is


psi

The slab is designed for a tensile stress of 197 psi.

If the tensile stress at the top of the slab (obtained from the charts below and entered above) is less than the design stress, the design is acceptable. If the check fails, new inputs have to be provided.


Corner Break Check:

PASS




1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm, $^{\circ}\text{C} = (^{\circ}\text{F} - 32)/1.8$

Figure 59. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for high-strength base and stiff subgrade.




1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm, $^{\circ}\text{C} = (^{\circ}\text{F} - 32)/1.8$

Figure 58. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for aggregate base and stiff subgrade.




1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm, $^{\circ}\text{C} = (^{\circ}\text{F} - 32)/1.8$

Figure 56. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for aggregate base and medium subgrade.




1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm, $^{\circ}\text{C} = (^{\circ}\text{F} - 32)/1.8$

Figure 57. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for high-strength base and medium subgrade.



1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm, $^{\circ}\text{C} = (^{\circ}\text{F} - 32)/1.8$

Figure 55. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for high-strength base and soft subgrade.



1 lbf = 4.45 N, 1 pci = 0.271 kPa/mm, 1 psi = 6.89 kPa, 1 in = 25.4 mm. °C = (°F - 32)/1.8

Figure S4. Tensile stress at top of slab for joint loading position, negative temperature differential, and full friction, for aggregate base and soft subgrade.

Rigid Pavement Design - Based on AASHTO Supplemental Guide

Reference: *LTPP DATA ANALYSIS - Phase I: Validation of Guidelines for k-Value Selection and Concrete Pavement Performance Prediction*

Results

Project #
Description: Design of approach pavements to Bridge Structure
Location: Region 6

Slab Thickness Design

Pavement Type	JPCP	
18-kip ESALs Over Initial Performance Period (million)	13.77	million
Initial Serviceability	4.5	
Terminal Serviceability	2.5	
28-day Mean PCC Modulus of Rupture	650	psi
Elastic Modulus of Slab	3,400,000	psi
Elastic Modulus of Base	15,000	psi
Base Thickness	6.0	in.
Mean Effective k-Value	175	psi/in
Reliability Level	95	%
Overall Standard Deviation	0.34	
Calculated Design Thickness	10.84	in

Temperature Differential

Mean Annual Wind Speed	8.8	mph
Mean Annual Air Temperature	50.3	°F
Mean Annual Precipitation	15.3	in
Maximum Positive Temperature Differential	8.28	°F

Modulus of Subgrade Reaction

<u>Period</u>	<u>Description</u>	<u>Subgrade k-Value, psi</u>
---------------	--------------------	------------------------------

Seasonally Adjusted Modulus of Subgrade Reaction psi/in

Modulus of Subgrade Reaction Adjusted for Rigid Layer
and Fill Section 190 psi/in

Traffic

Performance Period years

Two-Way ADT

Number of Lanes in Design Direction

Percent of All Trucks in Design Lane

Percent Trucks in Design Direction

<u>Vehicle Class</u>	<u>Percent of</u> <u>ADT</u>	<u>Annual</u> <u>Growth</u>	<u>Initial</u> <u>Truck Factor</u>	<u>Annual</u> <u>Growth in</u> <u>Truck Factor</u>	<u>Accumulated</u> <u>18-kip ESALs</u> (millions)
----------------------	---------------------------------	--------------------------------	---------------------------------------	--	---

Total Calculated Cumulative ESALs million

Faulting

Doweled

Dowel Diameter 1.5 in

Drainage Coefficient 1.00

Average Fault for Design Years with Design Inputs 0.06 in

Criteria Check PASS

Nondoweled

Drainage Coefficient 1

Average Fault for Design Years with Design Inputs in

Criteria Check